



City of Nashua

Central Purchasing

229 Main Street

Nashua, NH 03060

603-589-3330

Fax: 603-589-3344

April 12, 2010

SUBJECT: INVITATION FOR BID IFB0285-041510 Transit Center Improvements

ADDENDUM #2

Addendum #2 consists of the following:

IFB0285-041510 Addendum 2 (this document)	1 page
IFB0285-041510 Addendum 2 page 2	1 page
Total	2 pages

Information included in this document becomes a part of the original Invitation for Bid.

Please sign below to indicate receipt of this additional information and include this page with your submittal.

All other aspects of the original document remain the same.

Respectfully,

Mary Sanchez, CPPB
Purchasing Agent II
City of Nashua

Addendum #2 received and incorporated into bid submittal.

(Authorized Signature)

(Date)

ADDENDUM NUMBER 2:
IFB0285-041510
CITY OF NASHUA, NEW HAMPSHIRE
TRANSIT CENTER IMPROVEMENTS

Issued: April 12, 2010
For Bids Due: April 15, 2010

Division 1 -
Gener
al
Admi
nistra
tion

Section 001500 – Measurement and Payment

Revise 2.9 B to Read as Follows:

B. PAYMENT: Payment for this item will be full compensation for all labor, materials, and equipment required to complete all interior ceiling modifications including removal and disposal of existing gypsum ceiling, ceiling tiles and grid, framing and installing new gypsum ceiling in waiting area and corridor, installing new gypsum ceiling in restrooms and storage room, addition of gypsum wallboard and framing at walls for new ceiling height in waiting area, installing new ceiling tiles and grid in office area, removing and disposing of existing louvers, furnishing and installing new HVAC louvers and completing required ductwork connections, provide access panel, and all other appurtenant work in full conformance with the Drawings and Specifications.

Construction Drawings

Clarifications to Drawings:

- a. *Drawing A1-2: ACT-1 is to be Armstrong Dune Second Look II with 15/16 inch Armstrong Prelude grid. See specification Section 095100. Disregard Acoustical Panel Type II in Section 095100 which is not part of this contract.*
- b. *Drawing A1-2, Section 2: For installation of vapor barrier and insulation, access to Reception 102 and Lobby 101 would be from the attic areas on either side. All other areas would be accessed from below. The attic framing bottom chord is approximately 10'-0" above finish floor and is cold formed metal framing. Note that new ceilings are specified in Waiting 100, Office 108, Corridor 103, Storage 104, Public Restroom 107, and Staff Restroom 105.*
- c. *Drawing A1-4, Section 3: Steel tube sizes for installation of bird spikes is as follows: 6x6 tube at full length of centerline of canopy, 6x6 tube cantilevers on both sides of each post and 4x6 tubes at full length of eaves.*

Changes to Drawings

Drawing A1-3: Remove existing ceiling and install 5/8" mr gwb ceilings at Public Restroom 107 and Staff Restroom 105. New ceiling to match height of existing ceiling.

END OF ADDENDUM NO. 2